

PRC Environmental Management, Inc.
233 North Michigan Avenue
Suite 1621
Chicago, IL 60601
312-856-8700
Fax 312-938-0118



**PRELIMINARY ASSESSMENT/
VISUAL SITE INSPECTION**

**FALK CORPORATION
MILWAUKEE, WI
WID 006 097 083**

FINAL REPORT

EPA Region 5 Records Ctr.



361297

Prepared for

**U.S. ENVIRONMENTAL PROTECTION AGENCY
Office of Waste Programs Enforcement
Washington, DC 20460**

Work Assignment No.	:	C05087
EPA Region	:	5
Site No.	:	WID 006 097 083
Date Prepared	:	March 1, 1993
Contract No.	:	68-W9-0006
PRC No.	:	009-C05087WI4E
Prepared by	:	PRC Environmental Management, Inc. (Kurt Whitman)
Contractor Project Manager	:	Shin Ahn
Telephone No.	:	(312) 856-8700
EPA Work Assignment Manager	:	Kevin Pierard
Telephone No.	:	(312) 886-4448

101

LIST OF TABLES

<u>Table</u>		<u>Page</u>
1	SOLID WASTE MANAGEMENT UNITS	7
2	SOLID WASTES	10
3	SWMU AND AOC SUMMARY	36

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
1	FACILITY LOCATION	5
2	FACILITY LAYOUT, SWMUs 1 THROUGH 10	8
3	FACILITY LAYOUT, SWMU 11, SWMU 12, AND AOC 1	9

ENFORCEMENT
CONFIDENTIAL

EXECUTIVE SUMMARY

PRC Environmental Management, Inc. (PRC), performed a preliminary assessment and visual site inspection (PA/VSI) to identify and assess the existence and likelihood of releases from solid waste management units (SWMU) and other areas of concern (AOC) at the Falk Corporation (Falk) facility in Milwaukee, Milwaukee County, Wisconsin. This summary highlights the results of the PA/VSI and the potential for releases of hazardous wastes or hazardous constituents from SWMUs and AOCs identified. In addition, a completed U.S. Environmental Protection Agency (EPA) Preliminary Assessment Form (EPA Form 2070-12) is included in Attachment A to assist in prioritizing RCRA facilities for corrective action.

The Falk facility manufactures gears, gear drives, and flexible couplings for mechanical and hydropower transmission components. The facility consists of seven main areas: a foundry, machine shops, welding shop, heat treat shop, melt shop, storage, and the power house/boiler room. The facility generates and manages the following waste streams: (1) waste enamel paint and xylene (F003); (2) waste copper cyanide (P030); (3) spent mineral spirits (D001); (4) spent mineral spirits and 1,1,1-trichloroethane (D001 and F001); (5) used paint booth filters (nonhazardous); (6) spent refractory bricks (nonhazardous); (7) waste lapping compound (nonhazardous); (8) scrap metal chips and turnings (nonhazardous); (9) scrap metal pieces (nonhazardous); (10) waste soldering fluid (nonhazardous); (11) waste oil (nonhazardous); (12) waste shot blast (nonhazardous); (13) waste foundry sand and debris (nonhazardous); (14) waste slag and skulls (nonhazardous); (15) waste dry collector dust (nonhazardous); (16) waste wet collector dust (nonhazardous); (17) waste risers and gate cuttings (nonhazardous); (18) waste foundry sand washings (nonhazardous); (19) wastewater treatment plant sludge (nonhazardous); and (20) incinerator ash (nonhazardous).

The facility has operated at its current location since 1892. The facility occupies about 51 acres in a mixed-use area and employs about 1,300 people. The facility currently operates as a large-quantity generator storing hazardous waste for less than 90 days. Prior to 1989, the facility was regulated as a treatment, storage, or disposal facility.

In 1970, Falk was purchased by Sundstrand Corporation (Sundstrand) in Rockford, Illinois and is a wholly-owned subsidiary of Sundstrand.

RELEASED
DATE 2/2/91
RIN # WV
INITIALS WV

The PA/VSI identified the following twelve SWMUs and one AOC at the facility:

Solid Waste Management Units

1. Oil Storage Area
2. Metal Chip Storage Area
3. Solid Waste Refuse Dumpster and Compactor
4. Scrap Metal Storage Area
5. Shot Blast Storage Area
6. Foundry Sand Laundry Area
7. Wastewater Treatment Plant
8. Foundry Sand Tailings Area
9. Foundry Area (Foundry)
10. Former Incinerator Area (Incinerator)
11. Dry Dust Collectors (Dry DC)
12. Wet Dust Collectors (Wet DC)

Areas of Concern

1. Former Fuel Underground Storage Tanks (UST)

At the time of PRC's inspection, the facility was not in operation due to its annual 2-week plant shutdown. A secondary containment berm surrounds the perimeter of the entire facility. SWMUs 1 through 7 and 10 through 12 have a low potential for release to environmental media because the SWMUs have adequate containment. SWMU 1 underwent RCRA closure in 1988, which was approved by Wisconsin Department of Natural Resources in 1989. SWMU 10 is inactive and was removed by the facility in 1985.

SWMUs 8 and 9 have a moderate potential for release to an environmental media because waste foundry sand and debris is tracked across the facility. Therefore, there is inadequate containment for these two SWMUs, and thus is a potential for the release and off-site transportation of airborne dust.

The facility formerly had two fuel underground storage tanks (UST), an 8,000-gallon tank for unleaded gasoline, and a 12,000 gallon tank for leaded gasoline. On December 29, 1986, the piping from the 8,000-gallon unleaded gasoline UST was found to be leaking. The leak was repaired and no other release was detected. On August 17, 1987, the 12,000-gallon UST was removed from the Falk facility. On January 15, 1988, the 8,000-gallon UST was removed from the facility. These Former Fuel USTs (AOC 1) were replaced with one new UST, which is used

RELEASED ES-212101
DATE _____
RIN # _____
INITIALS CUV

ENFORCEMENT
CONFIDENTIAL

for the storage of unleaded gasoline. In 1986, a leak occurred in the piping system for unleaded gasoline UST; and the possibility exists that a release to on-site soils has occurred. On-site soils have not been analyzed for total petroleum hydrocarbons (TPH) or other compounds such as benzene, toluene, ethyl benzene, and xylene (BTEX). The potential for release to ground water from AOC 1 is moderate.

The nearest surface water body is the Menomonee River, which is immediately south and east of the facility. The Menomonee River is used for recreational and industrial water purposes. The nearest wetland is 1.7 miles northeast of the facility. Other sensitive environments are more than 5 miles away from the facility.

The nearest residence is about 0.2 miles north of the facility. Ground water within 2.5 miles of the facility is not used for drinking water.

PRC recommends that Falk take action to minimize the release of foundry waste and dust from SWMUs 8 and 9 across the facility and to potential off-site receptor areas. Falk also should collect on-site soil samples from the area where the Former Fuel USTs were located, to determine the extent of TPH and BTEX contamination.

RELEASED
DATE 2/21/01
RIN #
INITIALS CAV

ENFORCEMENT
CONFIDENTIAL

1.0 INTRODUCTION

PRC Environmental Management, Inc. (PRC), received Work Assignment No. C05087 from the U.S. Environmental Protection Agency (EPA) under Contract No. 68-W9-0006 (TES 9) to conduct preliminary assessments (PA) and visual site inspections (VSI) of hazardous waste treatment and storage facilities in Region 5.

As part of the EPA Region 5 Environmental Priorities Initiative, the RCRA and CERCLA programs are working together to identify and address RCRA facilities that have a high priority for corrective action using applicable RCRA and CERCLA authorities. The PA/VSI is the first step in the process of prioritizing facilities for corrective action. Through the PA/VSI process, enough information is obtained to characterize a facility's actual or potential releases to the environment from solid waste management units (SWMU) and areas of concern (AOC).

A SWMU is defined as any discernible unit at a RCRA facility in which solid wastes have been placed and from which hazardous constituents might migrate, regardless of whether the unit was intended to manage solid or hazardous waste.

The SWMU definition includes the following:

- RCRA-regulated units, such as container storage areas, tanks, surface impoundments, waste piles, land treatment units, landfills, incinerators, and underground injection wells
- Closed and abandoned units
- Recycling units, wastewater treatment units, and other units that EPA has usually exempted from standards applicable to hazardous waste management units
- Areas contaminated by routine and systematic releases of wastes or hazardous constituents. Such areas might include a wood preservative drippage area, a loading or unloading area, or an area where solvent used to wash large parts has continually dripped onto soils.

An AOC is defined as any area where a release of hazardous waste or constituents to the environment has occurred or is suspected to have occurred on a nonroutine and nonsystematic basis. This includes any area where a strong possibility exists that such a release might occur in the future.

The purpose of the PA is as follows:

- Identify SWMUs and AOCs at the facility
- Obtain information on the operational history of the facility
- Obtain information on releases from any units at the facility
- Identify data gaps and other informational needs to be filled during the VSI

The PA generally includes review of all relevant documents and files located at state offices and at the EPA Region 5 office in Chicago.

The purpose of the VSI is as follows:

- Identify SWMUs and AOCs not discovered during the PA
- Identify releases not discovered during the PA
- Provide a specific description of the environmental setting
- Provide information on release pathways and the potential for releases to each medium
- Confirm information obtained during the PA regarding operations, SWMUs, AOCs, and releases

The VSI includes interviewing appropriate facility staff; inspecting the entire facility to identify all SWMUs and AOCs; photographing all visible SWMUs; identifying evidence of releases; making a preliminary selection of potential sampling parameters and locations, if needed; and obtaining additional information necessary to complete the PA/VSI report.

This report documents the results of a PA/VSI of the Falk Corporation (Falk) facility (EPA Identification No. WID 006 097 083) in Milwaukee, Milwaukee County, Wisconsin. The PA was completed on July 21, 1992. PRC gathered and reviewed information from the Wisconsin Department of Natural Resources (WDNR), Federal Emergency Management Agency (FEMA), U.S. Geological Survey (USGS), U.S. Department of Agriculture (USDA), Wisconsin Wetlands Inventory (WWI), Wisconsin Geological Natural History Survey (WGNHS) and from EPA Region 5 RCRA files. The VSI was conducted on July 24, 1992. It included interviews with facility

representatives and a walk-through inspection of the facility. PRC identified twelve SWMUs and one AOC at the facility.

PRC completed EPA Form 2070-12 using information gathered during the PA/VSI. This form is included as Attachment A. The VSI is summarized and eighteen inspection photographs are included in Attachment B. Field notes from the VSI are included in Attachment C.

2.0 FACILITY DESCRIPTION

This section describes the facility's location; past and present operations; waste generating processes and waste management practices; a history of documented releases; regulatory history; environmental setting; and receptors.


2.1 FACILITY LOCATION

The Falk facility is located at 3001 W. Canal Street in Milwaukee, Milwaukee County, Wisconsin. Figure 1 shows the location of the facility in relation to the surrounding topographic features (latitude 43°01'46" N and longitude 87°57'04" W). The facility occupies about 51 acres in a mixed-use area.


The facility is bordered on the north by West Canal Street and Interstate Highway 94; on the west by a vacant lot; on the south by the Menomonee River; and on the east by the Soo Line Railroad Depot, Thiele Tanning Company (tannery), and A.L. Gebhardt Tanning Company (tannery).

2.2 FACILITY OPERATIONS

The Falk facility manufactures gears, gear drives, and flexible couplings for mechanical and hydropower transmission components. The facility consists of seven main areas: a foundry, machine shops, welding shop, heat treat shop, melt shop, storage, and the power house/boiler room. Foundry operations include mold and core making using sodium silicate sand and binders; steel metal melting and pouring; sand shakeout of molds and cores; finishing; cleaning; cutting; and welding. Machining operations include the grinding and cutting of the steel castings into manufactured products. The welding operation cuts, welds, and cleans steel castings into rough shaped metal components. The heat treat operation anneals (heat treats) steel castings in batch ovens using quench oil. The melting operation uses two electric arc furnaces to melt steel and recycled scrap steel. All raw materials and finished products are stored in warehouses. The power house/boiler room is used to generate electricity for the entire facility. Raw material used at the facility includes: steel; ferric chromium ore; ferro-manganese metal alloy; nickel ore; manganese ore; cooling and lubricating oils; silica sand; sodium silicate binder; propylene carbonate binder; grease; mineral spirits; lapping compound; soldering fluid with zinc chloride; enamel paints; water; no bake paste resins; xylene; and a mineral spirits and 1,1,1-trichloroethane mixture. Raw



SCALE 1:24000



SCALE 1"=2,000'



QUADRANGLE LOCATION

SOURCE: MODIFIED FROM USGS, MILWAUKEE QUADRANGLE, 1971

FALK CORPORATION
MILWAUKEE, WISCONSIN

FIGURE 1
FACILITY LOCATION

PRC ENVIRONMENTAL MANAGEMENT, INC.

materials are stored in drums and other storage containers throughout the facility. Unleaded gasoline and number 6 bunker fuel are stored in underground storage tanks (USTs).

Falk has operated at the facility since 1892 and employs about 1,300 people. The total square footage for the facility under roof is 1,051,528 (Falk, 1990). Parking lots are on the north end of the facility. A secondary containment berm surrounds the entire facility.

Falk has been in continuous operation as a foundry for about 100 years. Since 1970, the facility has been a wholly owned subsidiary of Sundstrand Corporation in Rockford, Illinois. Solid wastes generated from facility operations and the SWMUs where they are managed are discussed in detail in Section 2.3.

2.3 WASTE GENERATION AND MANAGEMENT

The primary waste generating processes at the Falk facility include the following: (1) painting operation; (2) parts heat treating operation; (3) melt shop operation; (4) parts cleaning and washing operation; (5) machining operation; (6) welding operation; (7) equipment oil draining; (8) blasting operation; (9) foundry operation; (10) air emission dust control systems; (11) laundry area; and (12) wastewater treatment plant. In the past the facility had an incineration operation.

Wastes are generated and managed at various locations at the facility. SWMUs and their current status are identified in Table 1. The locations of SWMUs in relation to the facility layout are shown on Figures 2 and 3. Wastes generated at the facility are summarized in Table 2. Facility generation and management of both hazardous and nonhazardous wastes, are discussed below.

Waste enamel paint and xylene (F003) (about 1,110 gallons per year), generated by the parts painting operation, is stored in drums at the Oil Storage Area (SWMU 1), and is transported off site by Safety-Kleen Corporation, of Dolton, Illinois, for recycle or disposal at their Illinois facility (Falk, 1992a).

Waste copper cyanide (P030) (about 10 pounds per year) in a drum, is generated by the heat treat shop and is stored at the Oil Storage Area (OSA) (SWMU 1). Waste copper cyanide has not been transported off site because Falk has not contracted with a disposal facility, however,

TABLE 1
SOLID WASTE MANAGEMENT UNITS

<u>SWMU Number</u>	<u>SWMU Name</u>	<u>RCRA Hazardous Waste Management Unit^a</u>	<u>Status</u>
1	Oil Storage Area	Yes	Active; underwent RCRA closure, approved in 1989. Currently regulated for less than 90-day storage of hazardous waste.
2	Metal Chip Storage Area	No	Active; storage of nonhazardous waste
3	Solid Waste Refuse Dumpster and Compactor	No	Active; storage of nonhazardous waste
4	Scrap Metal Storage Area	No	Active; storage of nonhazardous waste
5	Shot Blast Storage Area	No	Active; storage of nonhazardous waste
6	Foundry Sand Laundry Area	No	Active; cleaning of nonhazardous waste
7	Wastewater Treatment Plant	No	Active; storage and treatment of nonhazardous waste
8	Foundry Sand Tailings Area	No	Active; storage of nonhazardous waste
9	Foundry Area	No	Active; storage of nonhazardous waste
10	Former Incinerator Area	No	Inactive; removed in 1985
11	Dry Dust Collectors	No	Active; storage of nonhazardous waste
12	Wet Dust Collectors	No	Active; storage of nonhazardous waste

Note:


^a A RCRA hazardous waste management unit is one that currently requires or formerly required submittal of a RCRA Part A or Part B permit application.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
EXECUTIVE SUMMARY	ES-1
1.0 INTRODUCTION	1
2.0 FACILITY DESCRIPTION	4
2.1 FACILITY LOCATION	4
2.2 FACILITY OPERATIONS	4
2.3 WASTE GENERATION AND MANAGEMENT	6
2.4 HISTORY OF DOCUMENTED RELEASES	14
2.5 REGULATORY HISTORY	14
2.6 ENVIRONMENTAL SETTING	16
2.6.1 Climate	16
2.6.2 Flood Plain and Surface Water	17
2.6.3 Geology and Soils	17
2.6.4 Ground Water	18
2.7 RECEPTORS	18
3.0 SOLID WASTE MANAGEMENT UNITS	20
4.0 AREAS OF CONCERN	30
5.0 CONCLUSIONS AND RECOMMENDATIONS	31
REFERENCES	38

Attachment

- A EPA PRELIMINARY ASSESSMENT FORM 2070-12
- B VISUAL SITE INSPECTION SUMMARY AND PHOTOGRAPHS
- C VISUAL SITE INSPECTION FIELD NOTES



LEGEND

- SWMU 1 OIL STORAGE AREA
- SWMU 2 METAL CHIP STORAGE AREA
- SWMU 3 SOLID WASTE REFUSE DUMPSTER AND COMPACTOR
- SWMU 4 SCRAP METAL STORAGE AREA
- SWMU 5 SHOT BLAST STORAGE AREA
- SWMU 6 FOUNDRY SAND LAUNDRY AREA
- SWMU 7 WASTEWATER TREATMENT PLANT
- SWMU 8 FOUNDRY SAND TAILINGS AREA
- SWMU 9 FOUNDRY AREA
- SWMU 10 FORMER INCINERATOR AREA


NOT TO SCALE

FALK CORPORATION
MILWAUKEE, WISCONSIN

FIGURE 2
FACILITY LAYOUT-SWMUs 1 THROUGH 10

PRC ENVIRONMENTAL MANAGEMENT, INC.

FALK-3.DWG - 12/01/92 - CTR - 006-C05087M4E



LEGEND

- SWMU 11 DRY DUST COLLECTORS
- SWMU 12 WET DUST COLLECTORS
- AOC 1 FUEL UNDERGROUND STORAGE TANKS

NOT TO SCALE

FALK CORPORATION
MILWAUKEE, WISCONSIN

FIGURE 3
FACILITY LAYOUT-SWMU 11,
SWMU 12, AND AOC 1

PRC ENVIRONMENTAL MANAGEMENT, INC.

TABLE 2
SOLID WASTES

<u>Waste/EPA Waste Code^a</u>	<u>Source</u>	<u>Solid Waste Management Unit^b</u>
Waste enamel paint and xylene/F003	Painting operation	SWMU 1
Waste copper cyanide/P030	Heat treating operation	SWMU 1
Spent mineral spirits/D001	Cleaning and washing operation	None
Spent mineral spirits and 1,1,1-trichloroethane mixture/D001 and F001	Cleaning and washing operation	None
Used paint booth filters/NA	Painting operation	SWMU 3
Spent refractory bricks/NA	Heat treat and melt shop operations	SWMU 3
Waste lapping compound/NA	Machining operation	SWMU 1
Scrap metal chips and turnings/NA	Machining operation	SWMU 2
Scrap metal pieces/NA	Machining operation	SWMU 4
Waste soldering fluid/NA	Welding operation	SWMU 1
Waste oil/NA	Equipment oil draining operation	SWMU 1
Waste shot blast/NA	Blasting operation	SWMUs 5 and 9
Waste foundry sand and debris/NA	Foundry	SWMUs 6, 8, and 9
Waste slag and skulls/NA	Foundry	SWMU 9
Waste dry collector dust/NA	Air emission dust control systems	SWMUs 7, 9, and 11
Waste wet collector dust/NA	Air emission dust control systems	SWMUs 7, 9, and 12
Waste risers and gate cuttings/NA	Foundry	SWMUs 4 and 9

TABLE 2 (Continued)

SOLID WASTES

<u>Waste/EPA Waste Code^a</u>	<u>Source</u>	<u>Solid Waste Management Unit^b</u>
Waste foundry sand washings/NA	Laundry area	SWMUs 6 and 7
Wastewater treatment plant sludge/NA	Wastewater treatment plant	SWMU 7
Incinerator ash/NA	Former Incinerator	SWMU 10

Notes:

^a Not applicable (NA) designates nonhazardous waste.

^b "None" indicates that the waste stream is not managed on site.

Falk is in the process of selecting a disposal facility. At the time of the VSI, the waste copper cyanide had been stored at the OSA for less than 90 days. This waste has not been transported off site for disposal because Falk has not contracted with a disposal facility.

Spent mineral spirits (D001) and a mixture of spent mineral spirits and 1,1,1-trichloroethane (TCA) (D001 and F001) (13,970 gallons per year) in containers are generated by parts cleaning and washing. About 90 parts cleaning and washing stations are located throughout the facility and are managed by Milwaukee Solvent and Chemicals, Inc. (Milsolv). Both wastestreams are transported off site by Milsolv for recycling at their facility in Menomonee Falls, Wisconsin (Falk, 1992a).

Used paint booth filters (nonhazardous) (1,400 filters per year) are generated by the parts painting operation, disposed of in roll off containers at the Solid Waste Refuse Dumpster and Compactor (SWMU 3), and transported off site by Browning Ferris Industries (BFI) to BFI's landfill in East Troy, Wisconsin (Falk, 1992a). Spent refractory bricks (nonhazardous) (about 7 tons per year) in bulk, are generated by the replacement of refractory brick from heat treat and melt shop furnaces, disposed of in roll off containers at the Solid Waste Refuse Dumpster and Compactor (SWMU 3), and transported off site by United Commercial Transport, Inc. (UCT), Salem, Wisconsin, to Falk's Rawson Avenue Landfill in Oak Creek, Wisconsin. Waste lapping compound (nonhazardous) (about 5 cubic yards per year) in drums is generated by gear polishing and stored at the OSA (SWMU 1). This waste has not been transported off site because Falk has not contracted with a disposal facility.

Scrap metal chips and turnings (nonhazardous) (4,616 tons per year) in bulk are generated by gear and parts cutting, grinding, and polishing. The waste is stored in the Metal Chip Storage Areas (SWMU 2) and recycled at the melt shop. These wastes are also transported off site for recycling by Miller Compressing Company to their facility in Milwaukee, Wisconsin (Falk, 1992b). Scrap metal pieces (nonhazardous) (quantity unavailable) are generated by cutting and welding parts, stored in roll off containers or bins at the Scrap Metal Storage Area (SWMU 4), and recycled on site at the melt shop. Scrap metal chips and turnings (nonhazardous) and scrap metal pieces (nonhazardous) are returned to the original metal feed stock in the melt shop and recycled and mixed with original raw materials to form molten metal used in poured steel castings. (The melt shop is not a SWMU pursuant to the Code of Federal Regulation, Chapter 40, Part 261.2(e).)

A one time generation of 55-gallons of waste soldering fluid (nonhazardous) in drums occurred from parts welding in the weld shop, and was stored at the OSA (SWMU 1), and transported off site by Dahlen Transport, Inc. for disposal at Chem-Met Services, Inc. at Wyandotte, Michigan (Falk, 1992c).

Waste oil (nonhazardous) (24,450 gallons per year), is generated by the draining of machine gear boxes, compressors, fork lifts, and other lubricating and hydraulic sources. This waste is stored in bulk and drums at the OSA (SWMU 1) before being transported off site by Benz Oil, Inc. in Milwaukee, Wisconsin; Moreco Energy, Inc., in McCook, Illinois; or Rogers Oil, Inc., in Madison, Wisconsin. Each company transports to its respective facility for off-site recycling of waste oil (Falk, 1992b).

Waste shot blast (nonhazardous) in bulk is generated from the blasting and cleaning of parts with steel shot. This waste is stored in roll off boxes at the Shot Blast Storage Areas (SWMU 5) and the Foundry Area (SWMU 9). It is then recycled on site at the Shot Blast Storage Areas (SWMU 5) by vacuuming and removing the dust and returning the shot blast to the shot blast tables, or transported off site by UCT for disposal at Falk's Rawson Avenue Landfill (Falk, 1992b).

Waste foundry sand and debris (nonhazardous) in bulk is generated by the shakeout of sand moldings surrounding poured steel castings and the cleanup of waste foundry sand and debris. This waste is stored in loose piles, concrete boxes, and roll off bins at the Foundry Sand Tailings Area (SWMU 8) and the Foundry Area (SWMU 9). Waste foundry sand and debris is recycled and washed on site at the Foundry Sand Laundry Area (SWMU 6) or transported off site by UCT to Falk's Rawson Avenue Landfill.

Waste slag and skulls (nonhazardous) in bulk is generated by molten metal from foundry furnace and transport vessels. This waste is stored in the Foundry Area (SWMU 9). Waste dry and wet collector dust (nonhazardous) is generated by baghouse, cyclone, and wet scrubber air emission control systems in the Foundry Area (SWMU 9) and the machine, melt, and weld shops. The dust is stored in the Dry Dust Collectors (Dry DC) (SWMU 11), the Wet Dust Collectors (Wet DC) (SWMU 12), and the Foundry (SWMU 9). All waste dry and wet collector dust is treated on-site at the Wastewater Treatment Plant (SWMU 7). The waste dry and wet collector dust is used to solidify and stabilize the other foundry wastes sent to the Wastewater Treatment Plant (SWMU 7).

During 1991, about 33,408 tons of waste foundry sand and debris, waste slag and skulls, and dust were transported off site for disposal by UCT to Falk's Rawson Avenue Landfill (Falk, 1992b).

Waste risers and gate cuttings (nonhazardous) (quantity unavailable) are generated by the cutting and welding of poured castings in the Foundry Area (SWMU 9). This waste is stored in the Scrap Metal Storage Area (SWMU 4), and recycled on site by Falk at the melt shop. Waste foundry sand washings (nonhazardous) (quantity unavailable), in bulk, is generated by washing waste foundry sand and debris in the Foundry Sand Laundry Area (SWMU 6). This waste is transported to the Wastewater Treatment Plant (SWMU 7) for on-site treatment.

Wastewater Treatment Plant sludge (nonhazardous) (included in the waste foundry sand quantity) is generated by the combined physical treatment, mixing, and solidification using waste dry and wet collector dust, waste foundry sand washings, and treatment chemicals (i.e. polymers and alkaline materials). The sludge is stored in a treatment tank at the Wastewater Treatment Plant (SWMU 7) and transported off site for disposal by UCT to Falk's Rawson Avenue Landfill (Falk, 1992b).

In the past, incinerator ash (nonhazardous) (about 1,000 cubic yards before 1983) was generated by the on-site incineration of paper, plastic, and debris in the Former Incinerator Area (SWMU 10). The incinerator ash was transported off site for disposal by Waste Management of Wisconsin, Inc. (WMI) of Germantown, Wisconsin, to WMI's Germantown landfill (Falk, 1992c).

2.4 HISTORY OF DOCUMENTED RELEASES

The facility has no history of documented releases to ground water, surface water, air, or on-site soils.

2.5 REGULATORY HISTORY

Falk submitted a Notification of Hazardous Waste Activity form to EPA on August 25, 1980 (Falk, 1980a). Falk listed the facility as a treatment, storage, or disposal facility handling the following EPA hazardous waste codes: D001, F003, F005, F001, and F017. Falk submitted a RCRA Part A permit application on November 17, 1980 (Falk, 1980b).

The RCRA Part A permit application listed the following process codes and capacities: container storage (S01) for 11,000 gallons for SWMU 1. The RCRA Part A permit application listed the following EPA hazardous waste codes: F001, F003, F005, F017, and D001 (Falk, 1980b). A RCRA Part A permit application revision was sent to EPA and WDNR on December 3, 1981 which changed the container storage capacity to 4,000 gallons and deleted the EPA hazardous waste codes F001, F003, F005, and F017 (Falk, 1981). On February 24, 1982, Falk sent another RCRA Part A permit application revision to WDNR changing the container storage capacity to 2,000 gallons (Falk, 1982). Falk was sent an interim status letter from WDNR approving the storage of hazardous wastes on December 9, 1982 (WDNR, 1982a).

The facility RCRA closed the Oil Storage Area (OSA) (SWMU 1) on February 10, 1988 (Falk, 1988) and closure was approved by WDNR on January 12, 1989 (WDNR, 1989). The facility currently operates as a large-quantity generator.

In the past, Falk has been out of compliance with RCRA regulations. The facility was inspected by WDNR and EPA six times between 1981 and 1989. Falk was in RCRA compliance on three separate occasions (WDNR, 1982b, and 1985a; and EPA, 1981). WDNR compliance inspections in 1984, 1986, and 1988 revealed the facility was out of compliance with regulations pertaining to recordkeeping, closure plans, training, safety, and exceeding the waste storage capacity (WDNR, 1984a, 1984b, 1986a, and 1988). All RCRA violations were resolved by the facility and acknowledged by WDNR.

The facility is required to have an operating state air permit under facility identification number 241 008 240. This permit number regulates the following emission sources: boilers; electric arc furnaces; heat treat and core ovens; sand shakeout area; shot blast areas; and solvent metal cleaning (WDNR, 1992). The facility has not violated its air permits.

The facility has a history of odor complaints from area residents. Between 1981 and 1991, six formal complaint reports from residents were written up by WDNR personnel on odor and dust problems at the facility (WDNR, 1981, 1985b, 1985c, 1986b, 1991a, and 1991b).

The facility has a wastewater treatment plant (SWMU 7) which also treats waste from the facility's private storm and industrial sewer systems. The treated wastewater from the Wastewater Treatment Plant (SWMU 7) is discharged to the Milwaukee Metropolitan District sanitary sewer

system. The facility does not have a pretreatment permit for the discharge of wastewater to the local sanitary sewer system.

The facility has a Wisconsin Pollution Discharge Elimination (WPDES) permit (Permit Number WI-0001139-3) for a storm sewer water discharge to the Menomonee River from five outfall locations.

The facility removed two USTs between 1987 and 1988, and replaced them with one double-walled steel UST. The Former Fuel USTs (AOC 1) were removed prior to EPA's promulgation of UST regulations published in the Code of Federal Regulations, Title 40, Part 280. The Former Fuel USTs (AOC 1) consisted of an 8,000-gallon tank used to store unleaded gasoline and a 12,000-gallon tank that stored leaded gasoline. The new UST has cathodic protection, release detection, and double-walled construction. No record of release from the former USTs has been documented. However, on December 29, 1986, the Former Fuel USTs (AOC 1) were checked by Midwest Petroleum Services, Inc. (MPS) to determine structural integrity. MPS found a leak in the 8,000-gallon UST containing unleaded gasoline. The leak was repaired and no other release was detected by MPS or the facility. The on-site soils surrounding the USTs were never tested by Falk for the presence of TPH or BTEX. The Former Fuel USTs (AOC 1) did not undergo WDNR-approved closure (Falk, 1992d, and 1992e; PRC, 1992).

2.6 ENVIRONMENTAL SETTING

This section describes the climate; flood plain and surface water; geology and soils; and ground water in the vicinity of the facility.

2.6.1 Climate

The climate in Milwaukee County is continental. The average daily temperature is 46.9 degrees Fahrenheit (°F). The lowest average daily temperature is 29 °F in January. The highest average daily temperature is 84.1 °F in July (USDA, 1971).

The total annual precipitation for the county is 30.07 inches. The mean annual lake evaporation for the area is about 29 inches. The 1-year, 24-hour maximum rainfall is about 2.5 inches (U.S. Department of Commerce, 1963).

Prevailing winds are northwesterly from November through March, northeasterly from April through June, and southwesterly from July through October. During the windiest months - March, April, and November - the average wind speed is 14 miles per hour. June and July are the least windy months, with an average wind speed of about 10 miles per hour (USDA, 1971).

2.6.2 Flood Plain and Surface Water

Falk is located within a 100-year flood plain (FEMA, 1985). The nearest surface water body, the Menomonee River, is adjacent to and south of the facility and is used for recreational and industrial water purposes. The Menomonee River discharges to the Milwaukee River, which flows into Lake Michigan.

Surface water drains into the Menomonee River from the north to northwest by way of Falk's five WPDES-permitted storm sewer outfalls.

2.6.3 Geology and Soils

Surface soil and subsurface soils underlying the facility consist of a Ozaukee-Morley-Mequon Association with all subsoil of silty clay loam and clay. No other data on soil types and thicknesses are available because the facility is a heavy industrialized area where native soils have been displaced.

Although facility-specific information is not available, geological bedrock units in the general vicinity of the facility are known. Bedrock occurs immediately beneath glacial deposits and clay till (and gravel aquifer), 111 to 237 feet below ground surface (bgs). The bedrock is a Silurian-age dolomite of the Niagara, Alexandrian, and Erian Series. Only one well log within 1.0 mile of the facility contains confirming descriptions of glacial drift deposits underlain by limestone formation (Niagara Dolomite) (WGNHS, 1992). This well is not in operation and was abandoned when the city of Milwaukee converted to lake water. The Niagara Dolomite is 700 feet thick and is the most widely used source of generally good quality ground water (USGS, 1973).

Ordovician-age formations underlie the Niagara Dolomite. The uppermost formation is the Maquoketa Shale, a confining shale, up to 400 feet thick. This unit is underlain by the Sinnippee Group, consisting of Galena, Decorah, and Platteville Dolomites, with some limestone and shale. The Sinnippee Group is up to 340 feet thick. Underlying the Sinnippee Group is the

St. Peter sandstone and orthoquartzitic sandstone with minor limestone, shale, and conglomerate. This 330-foot thick formation is the most widely used unit of the sandstone aquifer (USGS, 1973). Although not in use as a source aquifer, the 140-foot thick Prairie du Chien Formation, underlying the St. Peter Formation, is commonly used in combination with the sandstone and Niagara aquifers. Five Cambrian sandstone formations do not yield much water. The sandstone formations are underlain by Precambrian-age crystalline rocks.

2.6.4 Ground Water

The sand and gravel aquifer is the uppermost aquifer, up to 237 feet bgs. The primary aquifer beneath the facility is the 700-foot thick Niagara Formation. Most wells in the Niagara aquifer produce at least 10 gallons per minute (gpm), and some high-capacity wells produce as much as 1,200 gpm. Water moves through cracks, crevices, and fractures; however, the distribution of these openings is not uniform in the Niagara aquifer, and well yields are not predictable. In most cases, recharge to the Niagara aquifer is local, and paths of movement are short. Ground water flows from west to east. Because much of the overburden is clay till, many parts of the Niagara aquifer are under artesian pressure. The potentiometric surface ranges from the top of the aquifer up to or above the land surface (USGS, 1973). Well logs from the area show an average static water level of about 72 feet bgs, which is about 20 feet above the top of the limestone (Niagara Dolomite) formation (WGNHS, 1992).

2.7 RECEPTORS

The facility occupies about 51 acres in a mixed-use area in Milwaukee, Wisconsin. Milwaukee has a population of about 628,000 (Rand McNally Corporation, 1992).

The facility is bordered on the north by West Canal Street and Interstate Highway 94; on the west by a vacant lot; on the south by the Menomonee River; and on the east by the Soo Line Railroad Depot, Thiele Tanning Company (tannery), and A.L. Gebhardt Tanning Company (tannery).

The nearest school, St. Rose School, is about 0.4 mile north of the facility. The facility has a barbed wire fence surrounding the property and 24-hour security guards. The nearest residence is about 0.2 mile north of the facility.

The nearest surface water body, the Menomonee River, is immediately adjacent to the facility on the south and east and is used for recreational and industrial water purposes. Other surface water bodies in the area include the Milwaukee River which is about 2.1 miles east and Lake Michigan which is about 2.5 miles east.

No ground-water drinking wells are within 2.5 miles of the facility. Drinking water is supplied by the city of Milwaukee from Lake Michigan (City of Milwaukee, 1992). Sensitive environments are not located on site. The nearest wetland is 1.7 miles northwest of the facility (WWI, 1982a and 1982b).

3.0 SOLID WASTE MANAGEMENT UNITS

This section describes the 12 SWMUs identified during the PA/VSI. The following information is presented for each SWMU: description of the unit, dates of operation, wastes managed, release controls, history of documented releases, and PRC's observations. Figures 2 and 3 show the SWMU locations.

SWMU 1

Oil Storage Area

Unit Description:

The unit is outdoors and is about 6 inches below ground surface. The unit measures about 30 by 30 feet. This unit is a pole-shed type structure and consists of an epoxy-sealed concrete floor with metal walls on three sides and a metal roof.

Date of Startup:

The unit began operation in about 1980.

Date of Closure:

The unit underwent RCRA closure in 1988, which was approved by WDNR in 1989.

Wastes Managed:

The unit manages waste enamel paint (F003); waste copper cyanide (P030); spent mineral spirits and 1,1,1-TCA mixture (D001 and F001); waste lapping compound (nonhazardous); waste soldering fluid (nonhazardous); and waste oil (nonhazardous). All wastes are managed in drums or in portable tanks (waste oil).

Release Controls:

The unit has an epoxy-sealed, sunken concrete floor and a concrete berm surrounding it. A metal roof and walls on three sides enclose the unit. No air emission controls exist for the unit. A floor drain leads to a sealed secondary spill containment sump. A secondary containment berm surrounds the entire facility.

History of Documented Releases:

No releases from the unit have been documented.

Observations: During the VSI, the unit contained about 30 drums of waste lapping compound; numerous 1- and 5-gallon cans of waste enamel paint with xylene; two drums of waste soldering fluid; one 1-gallon can of waste copper cyanide used in heat treating; and numerous drums and small, portable tanks of waste oil (see Photograph No. 1).

SWMU 2

Metal Chip Storage Area

Unit Description: The units are both indoors and outdoors, depending on the unit's location at the facility. All units are aboveground and consist of 20- to 40-cubic-yard metal roll off containers. The units are on either an asphalt or concrete pad. No floor drains are present near these units.

Date of Startup: The units began operation in about 1970.

Date of Closure: The units are active.

Wastes Managed: The units manage scrap metal chips and turnings.

Release Controls: The units only release controls is either an asphalt or concrete pad and a secondary containment berm that surrounds the entire facility.

History of Documented Release: No releases from these units have been documented.

Observations: During the VSI, the units contained scrap metal chips and turnings (nonhazardous) in 20- to 40-cubic-yard metal roll off containers. PRC observed no cracks or stains in the asphalt or concrete pads and no evidence of release (see Photograph No. 2).

SWMU 3**Solid Waste Refuse Dumpster and Compactor****Unit Description:**

The units are aboveground and outdoors, and consist of 20- to 40-cubic-yard metal roll off containers. The units are on either an asphalt or concrete pad. The units are located about 150 feet west of the facility's power house (see Figure 2). No floor drains are present near these units.

Date of Startup:

The units began operation in about 1970 (estimate).

Date of Closure:

The units are active.

Wastes Managed:

The units manage used paint booth filters (nonhazardous) and spent refractory bricks (nonhazardous).

Release Controls:

Release controls include either an asphalt or concrete pad and a secondary containment berm that surrounds the entire facility.

History of Documented Release:

No releases from these units have been documented.

Observations:

During the VSI, the units contained paper, and general refuse in a metal roll off container. PRC noted no evidence of release.

SWMU 4**Scrap Metal Storage Areas****Unit Description:**

Both units are aboveground and indoors. The units are located in the Foundry Area (SWMU 9) and the melt and weld shops. The units measure about 10 by 20 feet to about 60 by 60 feet in metal roll off containers or storage boxes. The units are situated on top of concrete pads. No floor drains are present near the units.

Date of Startup:

The units began operation in about 1970 (estimate).

Date of Closure:

The units are active.

Wastes Managed: The units manage scrap metal pieces (nonhazardous) and waste risers and gate cuttings (nonhazardous).

Release Controls: Release controls include a concrete floor and a secondary containment berm that surrounds the entire facility.

History of Documented Release: No releases from these units have been documented.

Observations: During the VSI, the units contained scrap steel metal in various sizes and shapes. No floor drains were visible. PRC noted no evidence of release (see Photographs No. 4 and 16).

SWMU 5 Shot Blast Storage Area

Unit Description: The two units are aboveground and indoors. The units measure about 4 by 6 feet and consist of metal bins above an epoxy-sealed concrete floor. No floor drains are located near these units.

Date of Startup: The units began operation in about 1940 (estimate).

Date of Closure: Both units are active.

Wastes Managed: Both units manage waste shot blast (nonhazardous).

Release Controls: Release controls include an epoxy-sealed concrete floor below the units and a secondary containment berm that surrounds the entire facility.

History of Documented Release: No releases from this unit have been documented.

Observations: During the VSI, PRC noted that the units contained waste shot blast spilled on the floor. Cracks are present in the concrete floor;

however, there are no stains in the concrete (see Photographs No. 6 and 15).

SWMU 6

Foundry Sand Laundry Area

Unit Description:

The unit is aboveground and indoors. The unit measures about 100 by 100 feet and consists of metal washing equipment. The unit is used to leach waste foundry sand and debris from the Foundry Area (SWMU 9). The washed foundry sand is recycled using water to wash the waste foundry sand and debris and then the foundry sand washings are transported to the Wastewater Treatment Plant (SWMU 7) by the facility.

Date of Startup:

The unit began operation in about 1970.

Date of Closure:

The unit is active.

Wastes Managed:

The unit manages waste foundry sand and debris (nonhazardous).

Release Controls:

Release controls include a concrete floor below the unit and a secondary containment berm that surrounds the entire facility.

History of Documented Release:

No releases from the unit have been documented.

Observations:

During the VSI, the unit was not in operation due to the facility's annual 2-week shutdown. PRC noted no evidence of release. No photograph was taken of this SWMU because it is located on the second floor of the Foundry Area (SWMU 9) and there was insufficient lighting to take a picture.

SWMU 7

Wastewater Treatment Plant

Unit Description:

The Wastewater Treatment Plant is aboveground and outside. The unit consists of concrete pads and three aboveground concrete tanks

and is about 80 by 70 feet. Capacities of each aboveground tank are unknown. The unit is used to physically treat and stabilize waste foundry sand washings transported from the Foundry Sand Laundry Area (SWMU 6), waste dry collector dust, and waste wet collector dust using alkalis and polymers. Waste dry and wet collector dust is used to stabilize and solidify all waste foundry sand washings.

Date of Startup:	The unit began operation in about 1970 (estimate).
Date of Closure:	The unit is active.
Wastes Managed:	The unit manages and treats waste foundry sand washings (nonhazardous), waste dry collector dust (nonhazardous), and waste wet collector dust. The stabilization process generates a wastewater treatment plant sludge (nonhazardous) that is stored in one of the aboveground, concrete tanks at this SWMU.
Release Controls:	Release controls include concrete pads below the unit and a secondary containment berm that surrounds the entire facility.
History of Documented Release:	No past releases from the unit have been documented.
Observations:	During the VSI, the unit contained wastewater treatment plant sludge. PRC observed no visible cracks in the wastewater treatment tanks and noted no evidence of release (see Photographs No. 7 and 9).
SWMU 8	Foundry Sand Tailings Area
Unit Description:	The unit is aboveground and outside, and consists of waste foundry sand that has fallen off the conveyor system that transports waste foundry sand to the Foundry Sand Laundry Area (SWMU 6). The waste foundry sand is stored in an uncontained waste pile, which is

about 2 by 15 feet. Waste foundry sand from this area is also stored in open-top metal bins about 20 feet east of the waste pile.

Date of Startup: The unit began operation in about 1970 (estimate).

Date of Closure: The unit is active.

Wastes Managed: The unit manages waste foundry sand (nonhazardous).

Release Controls: Release controls include an asphalt pad below the unit and a secondary containment berm that surrounds the entire facility.

History of Documented Release: No past releases from the unit have been documented.

Observations: During the VSI, the unit contained waste foundry sand and debris stored in an uncontained waste pile below the conveyor system and stored in open-top metal bins. The waste foundry sand and debris was tracked across an adjacent asphalt roadway and onto a gravel lot area. PRC noted that the size of the waste foundry sand and debris pile was about 20 by 20 feet by 3 feet (see Photographs No. 8 and 9).

SWMU 9

Foundry Area

Unit Description: The Foundry Area is both aboveground and belowground, and indoors. The belowground portion consists of pits used for the pouring and cooling of molten scrap and new steel into preformed sand castings. The pits are about 10 feet below ground. The overall size of this unit is 350 by 950 feet and consists of a metal roof, metal and concrete walls, and concrete floors.

Date of Startup: The unit began operation in about 1892.

Date of Closure: The unit is active.

Wastes Managed: The unit manages waste shot blast (nonhazardous); waste foundry sand and debris (nonhazardous); waste slag and skulls (nonhazardous); waste dry and wet collector dust (nonhazardous); and waste risers and gate cuttings (nonhazardous).

Release Controls: Release controls include dry and wet dust collectors, concrete floors, and a secondary containment berm that surrounds the entire facility.

History of Documented Release: No releases from the unit have been documented.

Observations: During the VSI, the unit contained scrap metal pieces, uncovered waste foundry sand and debris piles, waste slag and skulls, and waste scrap metal. PRC noted that there were visible cracks and pitted areas in the concrete floor throughout the Foundry Area. Poured steel castings were cooling in the pouring pits. Waste foundry sand and resulting dust was present throughout this SWMU (see Photographs No. 10 through 14). The foundry was not in operation during the VSI because the facility was on its annual 2-week shutdown.

SWMU 10

Former Incinerator Area

Unit Description: The Former Incinerator Area was aboveground and outside. The unit was about 6 by 20 feet (estimate) and was made of steel, concrete, and possibly bricks. The unit incinerated nonhazardous paper, wood, and general facility refuse.

Date of Startup: The unit began operation in about 1961.

Date of Closure: The unit ceased operation in 1985.

Wastes Managed: The unit managed incinerator ash (nonhazardous).

Release Controls: Release controls for the unit are unknown.

History of Documented Release: No releases from the unit have been documented.

Observations: During the VSI, PRC observed that the unit has been removed. PRC noted no evidence of release. No photograph was taken of this unit.

SWMU 11

Dry Dust Collectors

Unit Description: The units are indoors and aboveground. The units are located in the Foundry Area (SWMU 9) and the machine, melt and weld shops. The units measure 4 by 8 feet to 15 by 60 feet. The units are made up of two types of air collection systems: baghouse and cyclone dust collection systems.

Date of Startup: The units began operation in about 1960 (estimate).

Date of Closure: The units are active.

Wastes Managed: The units manage waste dry collector dust (nonhazardous).

Release Controls: Release controls include an asphalt or concrete pad below the unit, closed-top metal bins used to collect the dust, and a secondary containment berm that surrounds the entire facility.

History of Documented Release: No releases from these units have been documented.

Observations: During the VSI, the units contained dry collector dust in closed-top bins. Visible cracks in the concrete were noticed; however, PRC noted no evidence of release (see Photograph No. 18).

SWMU 12

Wet Dust Collectors

Unit Description: The units are indoors and aboveground. The units are located in the Foundry Area (SWMU 9) and the melt shop, and measure about 10 by 30 feet to 30 by 50 feet. The units consist of metal and concrete and have a concrete floor below them. No visible floor drains are near the units. Waste wet collector dust is from the wet scrubber air emissions control system and is stored in closed-top metal containers.

Date of Startup: The units began operation in about 1960.

Date of Closure: The units are active.

Wastes Managed: The units manage waste wet collector dust (nonhazardous).

Release Controls: Release controls include a concrete floor, closed-top metal containers, and a secondary containment berm that surrounds the entire facility.

History of Documented Release: No releases from these units have been documented.

Observations: During the VSI, the units were not in operation because of the facility's annual 2-week shutdown. PRC noted no evidence of release (see Photograph No. 14).

4.0 AREAS OF CONCERN

PRC identified one AOC during the PA/VSI. This AOC is discussed below; its location is shown in Figure 3.

AOC 1 **Former Fuel USTs**

The facility formerly had two fuel underground storage tanks (UST), an 8,000-gallon tank for unleaded gasoline, and a 12,000-gallon tank for leaded gasoline (Former Fuel USTs) (AOC 1). On December 29, 1986, the Former Fuel USTs (AOC 1) were checked by Midwest Petroleum Service, Inc. (MPS) to determine their structural integrity. MPS found a leak in the 8,000-gallon UST containing unleaded gasoline. The leak was found to be located in the piping system. MPS repaired the leak(s) and no further indication of leakage was found.

On August 17, 1987, the 12,000-gallon UST was removed from the Falk facility. On January 15, 1988, the 8,000-gallon UST was removed from the facility. These Former Fuel USTs (AOC 1) were replaced with one new UST, which is used for the storage of unleaded gasoline. In the process of removing the former USTs, Falk did not collect soil samples to confirm or deny the presence of TPH or BTEX in the surrounding excavated soil. Ground water monitoring wells were not installed to monitor for the potential of ground water contamination from TPHs. Falk removed the former USTs prior to EPA's promulgation of the UST regulations, which are published under the Code of Federal Regulations, Chapter 40, Part 280. The Former Fuel USTs were not approved for closure by EPA or WDNR. TPH or BTEX contamination of on-site soil has not been determined (Falk, 1992d; PRC, 1992).

5.0 CONCLUSIONS AND RECOMMENDATIONS

The PA/VSI identified 12 SWMUs and 1 AOC at the Falk facility. Background information on the facility's location; operations; waste generating processes and waste management practices; history of documented releases; regulatory history; environmental setting; and receptors is presented in Section 2.0. SWMU-specific information, such as the unit's description, dates of operation, wastes managed, release controls, history of documented releases, and observed condition, is presented in Section 3.0. AOCs are discussed in Section 4.0. Following are PRC's conclusions and recommendations for each SWMU and AOC. Table 3, at the end of this section, summarizes the SWMUs and AOC at the facility and the recommended further actions.

SWMU 1 Oil Storage Area

Conclusions: The Oil Storage Area is used for the less than 90-day storage of hazardous and solid wastes. The unit has a low potential for release to ground water, surface water, air, and on-site soils because the unit has an epoxy-sealed, sunken concrete floor and has a secondary containment berm surrounding the entire facility.

Recommendations: PRC recommends no further action for this SWMU.

SWMU 2 Metal Chip Storage Area

Conclusions: The Metal Chip Storage Area is used to store scrap metal chips and turnings from machining operations. The unit has a low potential for release to ground water, surface water, air, and on-site soils because the scrap metal chips and turnings are stored in metal roll off containers; the units have an asphalt or concrete pad and are indoors or outdoors and covered; and a secondary containment berm surrounds the entire facility.

Recommendations: PRC recommends no further action for this SWMU.

SWMU 3 Solid Waste Refuse Dumpster and Compactor

Conclusions: The Solid Waste Refuse Dumpster and Compactor is used for the disposal of nonhazardous spent refractory bricks and used paint booth filters. The unit has a low potential for release to ground water, surface water, air, and on-site soils because the nonhazardous waste is stored in closed-top metal roll off containers; the units have an asphalt or concrete pad; and a secondary containment berm surrounds the entire facility.

Recommendations: PRC recommends no further action for this SWMU.

SWMU 4 Scrap Metal Storage Area

Conclusions: The Scrap Metal Storage Area is used to store nonhazardous scrap metal pieces and waste risers and gate cuttings before on-site recycling in the melt shop. The two units have a low potential for release to ground water, surface water, air, and on-site soils because the units are indoors; and have concrete pads below the units; furthermore, a secondary containment berm surrounds the entire facility.

Recommendations: PRC recommends no further action for this SWMU.

SWMU 5 Shot Blast Storage Area

Conclusions: The Shot Blast Storage Area is used to store nonhazardous waste shot blast. The units have a low potential for release to ground water, surface water, air, and on-site soils because the units are indoors, have an epoxy-sealed concrete floor, waste is stored in metal bins, and a secondary containment berm surrounds the entire facility.

Recommendations: PRC recommends no further action for this SWMU.

SWMU 6 Foundry Sand Laundry Area

Conclusions: The Foundry Sand Laundry Area is used to wash waste foundry sand, which is then recycled by the facility. The unit has a low potential for release to ground water, surface water, air, and on-site soils because the

RELEASED
DATE 9/21/07
RIN #
INITIALS AAV

unit is indoors, has a concrete floor below it, and a secondary containment berm surrounds the entire facility.

Recommendations: PRC recommends no further action for this SWMU.

SWMU 7 Wastewater Treatment Plant

Conclusions: The Wastewater Treatment Plant is used to treat and stabilize various nonhazardous wastes. The unit has a low potential for release to ground water, surface water, air, and on-site soils because the unit has concrete pads below it, and a secondary containment berm surrounds the entire facility.

Recommendations: PRC recommends no further action for this SWMU.

SWMU 8 Foundry Sand Tailings Area

Conclusions: The Foundry Sand Tailings Area is aboveground and outside. The unit has a moderate potential for release to surface water, ground water, air, and on-site soils because release controls are inadequate and cannot prevent further on-site and off-site migration of waste foundry sand and debris.

Recommendations: PRC recommends that the facility prevent the future release of waste foundry sand by constructing a containment structure to hold the waste foundry sand, and covering the waste foundry sand to prevent an air release.

SWMU 9 Foundry Area

Conclusions: The Foundry Area has waste foundry sand and debris piles stored throughout the unit. The unit has a moderate potential for release to surface water, ground water, air, and on-site soils because (1) waste foundry sand can be discharged or tracked outside to the environment, and (2) there are numerous cracks and pitted areas in the concrete floor.

Recommendations: PRC recommends that the facility take corrective action to prevent future release of waste foundry sand to the environment. This may include sealing all cracks and pitted areas in the concrete floor, additional air emission control and dust suppression systems, and containing waste foundry sand and debris piles with barriers.

SWMU 10 Former Incinerator Area

Conclusions: The Former Incinerator Area was used to incinerate nonhazardous paper, wood, and general facility refuse. The unit has an unknown potential of release to ground water, surface water, air, and on-site soils because the unit was removed in 1985 and no EPA or WDNR documentation exists on the condition of the unit prior to removal.

Recommendations: PRC recommends no further action for this SWMU.

SWMU 11 Dry Dust Collectors

Conclusions: The Dry Dust Collectors are used to collect dry dust from the Foundry Area (SWMU 9), and the weld, machine, and melt shop area operations. The units have a low potential for release to ground water, surface water, air, and on-site soils because the units have a concrete pad below the units, the dust is contained in closed-top bins, most of the units are indoors, and there were no visible signs of release to the environment.

Recommendations: PRC recommends no further action for this SWMU.

SWMU 12 Wet Dust Collectors

Conclusions: The Wet Dust Collectors are used to remove and collect airborne dust from the melt shop and Foundry Area (SWMU 9). The units have a low potential for release to ground water, surface water, air, and on-site soils because the units have a concrete pad or floor below them, the dust from the wet scrubbers is contained, and the units are indoors.

**ENFORCEMENT
CONFIDENTIAL**

Recommendations: PRC recommends no further action for this SWMU.

AOC 1

Former Fuel USTs

Conclusions: The facility formerly had an 8,000-gallon UST for unleaded gasoline and a 12,000-gallon UST for leaded gasoline (Former Fuel USTs). On December 29, 1986, Falk's subcontractor, MPS, detected a leak in the 8,000-gallon UST. The leak was found to be located on the top of the tank, or in the piping system. MPS repaired the leak(s) and no further indication of leakage was found. However, the soils surrounding these USTs were not sampled or analyzed to verify or deny the potential contamination TPH or BTEX. In 1987, the 12,000-gallon UST was removed by the facility. In 1988, the 8,000-gallon UST was removed. The Former Fuel USTs were replaced with a double-steel walled UST with cathodic protection and release detection for unleaded gasoline.

Since a leak occurred in the piping system of the 8,000-gallon UST, the possibility exists that a release to on-site soils has occurred. The potential for release to ground water is moderate because there exists the possibility that TPH and BTEX contamination has occurred in the uppermost aquifer unit, which is the sand and gravel aquifer. Falk has not analyzed adjacent soils or ground water for TPH and BTEX contamination.

The potential for release to surface water and air is low because the leak from the 8,000-gallon UST occurred below ground surface.

Recommendations: PRC recommends that Falk sample the surrounding on-site soils where the Former Fuel USTs were located. Each sample should be analyzed for TPH and BTEX.

RELEASED
DATE 2/2/01
RIN #
INITIALS WV

ENFORCEMENT
CONFIDENTIAL

TABLE 3
SWMU AND AOC SUMMARY

<u>SWMU</u>	<u>Dates of Operation</u>	<u>Evidence of Release</u>	<u>Recommended Further Action</u>
1. Oil Storage Area	1980 to present	None	No further action required at this time
2. Metal Chip Storage Area	About 1970 to present	None	No further action required at this time
3. Solid Waste Refuse Dumpster and Compactor	About 1970 to present	None	No further action required at this time
4. Scrap Metal Storage Area	About 1970 to present	None	No further action required at this time
5. Shot Blast Storage Area	About 1940 to present	None	No further action required at this time
6. Foundry Sand Laundry Area	About 1970 to present	None	No further action required at this time
7. Wastewater Treatment Plant	About 1970 to present	None	No further action required at this time
8. Foundry Sand Tailings Area	About 1970 to present	None	Construct a containment structure to prevent future release of foundry sand and cover the waste foundry sand to prevent an air release

RELEASED
DATE 9/2/01
RIN #
INITIALS del/v

ENFORCEMENT
CONFIDENTIAL

TABLE 3 (Continued)
SWMU AND AOC SUMMARY

<u>SWMU</u>	<u>Dates of Operation</u>	<u>Evidence of Release</u>	<u>Recommended Further Action</u>
9. Foundry Area	1892 to present	None	Seal all cracks and pitted areas in the concrete floor, add additional air emission control, dust suppression systems, and contain the waste foundry sand and debris piles with barriers
10. Former Incinerator Area	1961 to 1985	None	No further action required at this time
11. Dry Dust Collectors	About 1960 to present	None	No further action required at this time
12. Wet Dust Collectors	About 1960 to present	None	No further action required at this time
<u>AOC</u>	<u>Dates of Operation</u>	<u>Evidence of Release</u>	<u>Recommended Further Action</u>
1. Former Fuel USTs	About 1960 to 1988	The facility documented the release of unleaded gasoline from a UST and on-site soils were not sampled or analyzed for TPH and BTEX	Collect soil samples around the location of the Former Fuel USTs to determine extent of TPH and BTEX contamination

RELEASED
DATE 2/2/01
RIN # AA
INITIALS AA

REFERENCES

- City of Milwaukee, 1992. Private and Commercial Well Listing for the City of Milwaukee, Wisconsin, January 24.
- Falk Corporation (Falk), 1980a. Notification of Hazardous Waste Activity, August 25.
- Falk, 1980b. RCRA Part A Permit Application, November 17.
- Falk, 1981. Revised RCRA Part A Permit Application, December 3.
- Falk, 1982. Revised RCRA Part A Permit Application, February 24.
- Falk, 1988. Letter from Kenneth G. Fries to Patrick Brady, Wisconsin Department of Natural Resources (WDNR), February 10.
- Falk, 1990. Summary Sheet of Total Square Footage Area for Falk, November.
- Falk, 1992a. Hazardous Waste Identification and Certification Report, February 25.
- Falk, 1992b. Letter from Kenneth G. Fries to Kurt Whitman, PRC Environmental Management, Inc. (PRC), July 31.
- Falk, 1992c. Letter from Kenneth G. Fries to Kurt Whitman, PRC, September 25.
- Falk, 1992d. Letter from Kenneth G. Fries to Kurt Whitman, PRC, October 15.
- Falk, 1992e. Letter from Kenneth G. Fries to Kurt Whitman, PRC, November 19.
- Federal Emergency Management Agency (FEMA), 1985. Flood Insurance Rate Map, City of Milwaukee, Wisconsin, Milwaukee and Washington Counties, Community Panel Number 550278-0013C, November 15.
- PRC Environmental Management, Inc. (PRC), 1992. Kurt Whitman Telephone Conversation with Kenneth Fries, Falk, October 28.
- Rand McNally Corporation, 1992. Road Atlas for the United States, Canada, and Mexico, Index to the United States Cities and Towns, January.
- U.S. Department of Agriculture (USDA), 1971. Soil survey of Milwaukee and Waukesha Counties, Wisconsin, July.
- U.S. Department of Commerce (USDC), 1963. Rainfall Frequency Atlas of the United States, Technical Paper Number 40.
- U.S. Environmental Protection Agency (EPA), 1981. Memorandum from Arnold E. Leder to Robert Krill, WDNR, October 15.
- U.S. Geological Survey (USGS), 1971. Milwaukee Quadrangle, Wisconsin - Milwaukee County.

USGS, 1973. Water Resources of Wisconsin - Lake Michigan Basin, Hydrologic Investigations, Atlas HA-432.

Wisconsin Department of Natural Resources (WDNR), 1981. Complaint/Inquiry Report Form, July 16.

WDNR, 1982a. Letter from Arthur Glor, Jr. to Frank Hartay, Falk, December 9.

WDNR, 1982b. Letter from James Reyburn to James Bauerschmidt, Falk, April 16.

WDNR, 1984a. WDNR Information Audit and Review done by Gary Edelstien for Falk, June 12.

WDNR, 1984b. Letter from Ken Hein to James Bauerschmidt, Falk, April 30.

WDNR, 1985a. Letter from Elizabeth Duchelle to Kenneth G. Fries, Falk, September 25.

WDNR, 1985b. Entity Contact Report Form, June 4.

WDNR, 1985c. Complaint/Inquiry Report Form, June 27.

WDNR, 1986a. Hazardous Waste Compliance Monitoring and Enforcement Summary for Falk, August 7.

WDNR, 1986b. Complaint/Inquiry Report Form, April 1.

WDNR, 1988. Letter from Richard Brown to Don Paulus, Falk, January 4.

WDNR, 1989. Letter from Franklin C. Schultz to Don Paulus, Falk, January 12.

WDNR, 1991a. Complaint/Inquiry Report Form, May 21.

WDNR, 1991b. Complaint/Inquiry Report Form, May 22.

WDNR, 1992. Air Compliance Inspection Report for Falk Corporation, Plant 1, April 29.

Wisconsin Geological and Natural History Survey (WGNHS), 1992. Geological and Water Well Logs for Township 7 North, Range 21 East, Sections 25, 30, and 35, open file, reviewed May 27.

Wisconsin Wetlands Inventory (WWI), 1982a. National Wetlands Inventory Map, Township 7, Range 21 East, Milwaukee County, Wisconsin, January.

Wisconsin Wetlands Inventory (WWI), 1982b. National Wetlands Inventory Map, Township 7 North, Range 22 East, Milwaukee County, Wisconsin, January.

ATTACHMENT A
EPA PRELIMINARY ASSESSMENT FORM 2070-12



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION

01 STATE
WI

02 SITE NUMBER
WID 006 097 083

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site)
Falk Corporation

02 STREET, ROUTE NO. OR SPECIFIC LOCATION IDENTIFIER
3001 West Canal Street

03 CITY
Milwaukee

04 STATE
WI

05 ZIP CODE
53201

06 COUNTY
Milwaukee

07 COUNTY CODE
07

08 CONG DIST
05

09 COORDINATES: LATITUDE
43°01'46"N

LONGITUDE
87°57'04"W

10 DIRECTIONS TO SITE (Starting from nearest public road)
Take Interstate Hwy. 94 (east or west) to North 27th St. Proceed north on 27th St. to Michigan Ave. Turn right (east) on Michigan Ave. to 25th St. Turn right (south) on 25th St. until you reach Canal St. Turn left and then immediately right to Falk.

III. RESPONSIBLE PARTIES

01 OWNER (if known)
Sundstrand Corporation

02 STREET (Business, mailing residential)
P.O. Box 5247

03 CITY
Rockford

04 STATE
IL

05 ZIP CODE
61125-0247

06 TELEPHONE NUMBER
(800) 638-6116

07 OPERATOR (if known and different from owner)
Same

08 STREET (Business, mailing, residential)

09 CITY

10 STATE

11 ZIP CODE

12 TELEPHONE NUMBER

13 TYPE OF OWNERSHIP (Check one)
☒ A. PRIVATE ☐ B. FEDERAL: _____ (Agency Name)
☐ C. STATE ☐ D. COUNTY ☐ E. MUNICIPAL
☐ F. OTHER _____ (Specify)
☐ G. UNKNOWN

14. OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)
☒ A. RCRA 3010 DATE RECEIVED: 08 / 20 / 80 MONTH DAY YEAR ☐ B. UNCONTROLLED WASTE SITE (CERCLA 103 c) DATE RECEIVED: ____ / ____ / ____ MONTH DAY YEAR ☐ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION BY (Check all that apply)
☒ A. EPA ☒ B. EPA CONTRACTOR ☐ C. STATE ☐ D. OTHER CONTRACTOR
☒ YES DATE 07/24/92 ☐ E. LOCAL HEALTH OFFICIAL ☐ F. OTHER: _____ (Specify)
☐ NO
CONTRACTOR NAME(S): PRC Environmental Management, Inc. (PRC)

02 SITE STATUS (Check one)
☒ A. ACTIVE ☐ B. INACTIVE ☐ C. UNKNOWN

03 YEARS OF OPERATION
1982 (Present) ☐ UNKNOWN
BEGINNING YEAR ENDING YEAR

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED
Waste enamel, paint and xylene (F003); used paint booth filters (nonhazardous); waste copper cyanide (P030); spent refractory bricks (nonhazardous); spent mineral spirits (D001); spent mineral spirits and 1,1,1-trichloroethane (D001 and F001); waste lapping compound (nonhazardous); scrap metal chips and turnings (nonhazardous); waste soldering fluid (nonhazardous); waste oil (nonhazardous); waste foundry sand, sweepings, debris, slag, skulls, risers, and gate cuttings (nonhazardous); waste dry and wet collector dust (nonhazardous); waste foundry sand washings (nonhazardous); wastewater treatment sludge (nonhazardous); and incinerator ash (nonhazardous).

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION
Overall potential for release to environmental media is moderate. The greatest hazard to the environment is off-site dust contamination from various foundry wastes. Airborne dust can be carried to residential population areas, which are located within 0.5 mile of the facility. Between 1987 and 1988, two Underground Storage Tanks (USTs) were removed by the facility. No laboratory testing was done on the on-site soils next to the USTs to confirm or deny the presence of total petroleum hydrocarbons or benzene, toluene, ethylbenzene, or xylene, although a piping system associated with one of the tanks is known to have leaked.

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents.)
☐ A. HIGH (Inspection required promptly) ☒ B. MEDIUM (Inspection required) ☐ C. LOW (Inspect on time-available basis) ☐ D. NONE (No further action needed; complete current disposition form)

VI. INFORMATION AVAILABLE FROM

01 CONTACT
Kevin Pierard

02 OF (Agency/Organization)
U.S. EPA

03 TELEPHONE NUMBER
(312) 886-4448

04 PERSON RESPONSIBLE FOR ASSESSMENT
Kurt E. Whitman

05 AGENCY

06 ORGANIZATION
PRC

07 TELEPHONE NUMBER
(414) 821-5894

08 DATE
12 / 22 / 92
MONTH DAY YEAR

II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

01 PHYSICAL STATES (Check all that apply)

- ☐ A. SOLID ☐ E. SLURRY
☐ B. POWDER, FINES ☐ F. LIQUID
☐ C. SLUDGE ☐ G. GAS

☐ D. OTHER _____
(Specify)

02 WASTE QUANTITY AT SITE

(Measures of waste quantities must be independent)

TON _____ None

CUBIC YARDS None

NO. OF DRUMS About 20

03 WASTE CHARACTERISTICS (Check all that apply)

- ☐ A. TOXIC ☐ H. IGNITABLE
☐ B. CORROSIVE ☐ I. HIGHLY VOLATILE
☐ C. RADIOACTIVE ☐ J. EXPLOSIVE
☐ D. PERSISTENT ☐ K. REACTIVE
☐ E. SOLUBLE ☐ L. INCOMPATIBLE
☐ F. INFECTIOUS ☐ M. NOT APPLICABLE
☐ G. INFLAMMABLE

III. WASTE TYPE

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE			
OLW	OILY WASTE			
SOL	SOLVENTS	1,100	Gallons	
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS	10	Pounds	
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

[illegible]

V. FEEDSTOCKS (See Appendix for CAS Numbers)

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

VI. SOURCES OF INFORMATION (Cite specific references; e.g., state files, sample analysis, reports)

Falk Corporation, 1992. Hazardous Waste Identification and Certification Report, February 25.
Wisconsin Department of Natural Resources. Hazardous Waste Files



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE
WT

02 SITE NUMBER
WID 006 097 081

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: Unknown 04 NARRATIVE DESCRIPTION

Two underground storage tanks containing unleaded gasoline and diesel fuel were removed in 1986, however, the on-site groundwater was not tested for total petroleum hydrocarbons. In addition, the piping from an 8,000-gallon unleaded gasoline underground storage tank leaked.

01 ☐ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None

01 ☐ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None

01 ☒ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: 1 to 5 04 NARRATIVE DESCRIPTION
(Acres)

Two underground storage tanks containing unleaded gasoline and diesel fuel were removed in 1986, however, the on-site soil was not tested for total petroleum hydrocarbons. In addition, an 8,000-gallon unleaded gasoline underground storage tank leaked.

01 ☐ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None

01 ☐ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE
WI

02 SITE NUMBER
WID 006 097 083

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

01 ☐ M. UNSTABLE CONTAINMENT OF WASTES

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: Unknown

04

NARRATIVE DESCRIPTION

Dust from waste foundry sand and debris can become airborne, where it will be carried off-site to residential areas and adjacent manufacturing operation facilities.

01 ☐ N. DAMAGE TO OFF-SITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

01 ☐ O. CONTAMINATION OF SEWERS, DRAINS, WWTPS
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: Unknown

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references; e.g., state files, sample analysis, reports)

Wisconsin Department of Natural Resources File Review.

ATTACHMENT B
VISUAL SITE INSPECTION SUMMARY AND PHOTOGRAPHS

VISUAL SITE INSPECTION SUMMARY

Falk Corporation
3001 West Canal Street
Milwaukee, WI 53201
WID 006 097 083

Date: July 24, 1992

Primary Facility Representative: Donald Paulus, Environmental Engineer
Representative Telephone No.: (414) 937-4371
Additional Facility Representatives: Kenneth Fries, Environmental Engineer

Inspection Team: Kurt Whitman, PRC Environmental Management, Inc.
(PRC)
Trent Schade, PRC

Photographer: Kurt Whitman, PRC

Weather Conditions: Calm, sunny, temperature about 75 °F

Summary of Activities: The visual site inspection (VSI) began at 8:30 a.m. with an introductory meeting. The inspection team explained the purpose of the VSI and the agenda for the visit. Facility representatives then discussed the facility's past and current operations, solid wastes generated, and release history. Facility representatives provided the inspection team with copies of requested documents.

The VSI tour began at 9:30 a.m. Falk representatives stated that the facility was in the middle of an annual 2-week plant shutdown. PRC began its inspection at the Oil Storage Area (OSA) (SWMU 1). PRC visited the Metal Chip Storage Area (SWMU 2); the Former Incinerator Area (SWMU 10); the machine shops; the facility's boiler room and power house areas; the heat treat shop areas; paint booth operations; the paint storage area; weld shop building; Dry Dust Collectors (SWMU 11); Shot Blast Area (SWMU 5); Scrap Metal Storage Area (SWMU 4); the Foundry Sand Laundry Area (SWMU 6); the Wastewater Treatment Plant (SWMU 7); the Foundry Sand Tailings Area (SWMU 8); the Foundry Area (SWMU 9); and the Wet Dust Collectors (SWMU 12).

The tour concluded at 12:29 p.m., after which the inspection team held an exit meeting with facility representatives. The VSI was completed and the inspection team left the facility at 12:40 p.m.



Photograph No. 1

Orientation: Southwest

Location: SWMU 1

Date: July 24, 1992

Description: This is a photograph of the Oil Storage Area. Drums of enamel paint, waste lapping compound, waste soldering fluid, waste copper cyanide, and virgin products are stored in this area.




Photograph No. 2

Orientation: Southeast

Location: SWMU 2

Date: July 24, 1992

Description: This is a photograph of one of the Scrap Metal Chip Storage Areas. The scrap metal from the machining operations is stored throughout the plant in metal roll off boxes like this one.



Photograph No. 3

Orientation: Northeast

Location: Spray Paint Booth

Date: July 24, 1992

Description: This is a photograph of a paint booth in machine shop number 2. Note the paint filter attached to the back of the unit.




Photograph No. 4

Orientation: West

Location: SWMU 4

Date: July 24, 1992

Description: This is a photograph of one of the Scrap Metal Storage Areas.



Photograph No. 5

Orientation: Southeast

Location: SWMU 11

Date: July 24, 1992

Description: This is a photograph of one of the Dry Dust Collectors from shot blasting and waste shot blast.



Photograph No. 6

Orientation: South-southeast

Location: SWMU 5

Date: July 24, 1992

Description: This is a photograph of one of the Shot Blast Storage Areas. Shot blast is stored in small metal bins.




Photograph No. 7

Orientation: North

Description: This is a photograph of the Wastewater Treatment Plant. Metal forming for steel castings are stored south of the Wastewater Treatment Plant.

Location: SWMU 7

Date: July 24, 1992



Photograph No. 8

Orientation: West

Description: This is a photograph of the Foundry Sand Tailings Area. The pile of waste foundry sand is about 2 by 15 feet.

Location: SWMU 8

Date: July 24, 1992



Photograph No. 9

Location: SWMUs 7 and 8

Orientation: Northeast

Date: July 24, 1992

Description: This is a photograph of the other Foundry Sand Tailings Area behind the 55-gallon drums in metal roll off containers. In the background is the Wastewater Treatment Plant (SWMU 7). The 55-gallon drums contain virgin baked resin.




Photograph No. 10

Location: SWMU 9

Orientation: East

Date: July 24, 1992

Description: This is a photograph of the Foundry Area, where waste foundry sand is stored in piles.



Photograph No. 11

Orientation: East-northeast

Description: This is a photograph of slag metal stored in the Foundry.

Location: SWMU 9

Date: July 24, 1992




Photograph No. 12

Orientation: South-southeast

Description: This is a photograph of the waste foundry sand stored in a permanent metal storage box. The waste foundry sand will be transferred to the Foundry Sand Laundry Area (SWMU 6) for washing.

Location: SWMU 9

Date: July 24, 1992



Photograph No. 13

Orientation: South-southeast

Location: SWMU 9

Date: July 24, 1992

Description: This is a close-up photograph of waste foundry sand stored in a permanent storage box. See Photograph No. 12, also.




Photograph No. 14

Orientation: East

Location: SWMU 9

Date: July 24, 1992

Description: This is a photograph taken from the west end of the Foundry. The waste foundry sand and debris, waste slag and skulls, scrap metal, and waste risers and gate cuttings are stored in a pile. A wet dust collector is located in the far left of the photograph.



Photograph No. 15

Orientation: Southwest

Location: SWMUs 5 and 9

Date: July 24, 1992

Description: This is a photograph of a Shot Blast Storage Area in the Foundry Area(SWMU 9). Waste shot blast has spilled onto the concrete floor in this area.



Photograph No. 16

Orientation: Northeast

Location: SWMU 4

Date: July 24, 1992

Description: This is a photograph of a Scrap Metal Storage Area adjacent to the facility's melt shop operation. Scrap metal is stored in large bins.




Photograph No. 17

Orientation: Northeast

Location: SWMU 5

Date: July 24, 1992

Description: This is a photograph of a Shot Blast Storage Area on the south central side of the Foundry Area (SWMU 9). Waste shot blast has spilled on the concrete floor.



Photograph No. 18

Orientation: South-southwest

Location: SWMU 11

Date: July 24, 1992

Description: This is a photograph of two dry dust collectors on the south-central side of the Foundry Area (SWMU 9).

ATTACHMENT C
VISUAL SITE INSPECTION FIELD NOTES

0800 hrs

Folk Corporation

3001 W - Canal St.

7-24-92

nr/w	wz
------	----

PA/VSF

to the North ^{1-north} 13 Red Star Years

Also To the north of Folk is
W. Canal Street and Hwy 94, to
the east is Thiele, Tanning + Sooline.

Capt. Company & A. L. Gebhardt, Tuging Co.,
Chillicothe, Mo.

to the west ^{at vacant lot and} ILCMC Waste Water Treatment Facility, Arad West Port, ^{ILCMC}

Person/ing Inc. & Great Lakes 12FW 7-24-02

~~Apartment Contractors~~

0830 hrs

Meeting with faculty

Representatives Kenneth Fries, Don Parker
and Jack Habrat. Discussed purpose

of PA/VSE, There is a total of 1,051,528 square feet under roof

KBW

including foundry, mach. shop. office &
weld shop.

1) Raw materials used for processes:

b) Arc melting Process - charged
Scrap metal (steel) . Rhyolite brick
from machine shop Electro

b) World Shop - 'reaching script
photo cutting

c)	Machine Shop		
----	--------------	--	--

Other materials used

Ferro - Manganese metal

Chromium Ore

Nickel

Manganese

d.) Heat Treat thru heating
& carburizing. Heat & Oil
Quench Treat.

KBW

96 3

Normal gas & #6 fuel oil.
Laboratory's are physical testing only

2 PCB transformers on site. Scheduled
out of service 1 this year and
1 next year.

Enamel painting done

- Water treatment from WPA
scrubbers (shakers) and
Sand Laundry where the
sand is re-washed and reused.

- Silica sand is used on site

- Additives used are a sodium
silicate binder & is reactive
with propylene carbonate hardener
Degreasing & cleaning is done
throughout the plant

KFW

97 4

Using mineral spirits and
a blend with TCA & mineral
spirits (2500 TCA)

Foundry waste (sand, spent
refractories, & slag, wet & dry
dust collectors, sweepings) are
sent to Falls land fill located
on 13th & Ransom Ave. Transporter
is United Commercial Transport, out
of Salem, Wisconsin

Lubricants include grease, cutting
oils and quench oils & coolants
(Semi-synthetic oils).

All scrap metal sent off site
is sent to Miller Compressing
doing a small amount of work

KFW

98x

with aluminum & brass parts that
are machined on site.

Safety clean Klean
remover paint water and other
solvents.

mil solv takes mineral spirits
& thinner the solvents

used in parts washer and
there is no storage of
solvents. Solvents are pumped
and are not stored in drums.

2 UST's - 1 diesel and 1
unleaded gas (1000 gal) Tanks were
installed in late 1987,
leak detection double wall
tanks, cathodically protected &
monitoring & mw around tank areas.

KEW

99x

Piping on US 19 is secondary lined.
Steel tanks.

The potential exists that formerly
sand was used for diking along
Memomene River & throughout the
plant as fill material. The plant

is 100 years. Falk has their

own storm water collection system
with 5 outfalls using pumps.

WIPES permit number #WI-0001139

-3

CMC stands for Chicago Milwaukee
Corporation

0030 End discussion and site tour

51 acres total and

About 1300 employees.

0941

Oil Storage Area.

Sampled floor surface concrete

floor, metal sides & metal on floor.

metal sides on 3 sides. Sideside of room

KEW

Sealed Floor NO cracks in floor 100 X

Heat Sensors for fire detection to
alarm system. 6 water sensors
Virgin materials KOT & Bury? collision
cleaners, oils, lubricants

Drain Gump capture waste
& materials not attached to

anything. Unmixed virgin material also
PIC 1 SW exposure of CSA

(Drum storage, Water present
are enamel paints in 1 & 5 gallon
containers are found in 55 gallon drums,
lapping compound, Solubility fluid
with Zn Cl₂, heat treat waste
(Cyanide Copper), 1 & 5 gallon
cans & lapping compounds
are not labeled with haz. or
non haz labels, Also some
in 40 kg reliefs are chips
going to miller composition &

KFW

has to not stop on west end
if OSA, Waste oil stored
outside. Oil recycling is

Benz oil & kerosene oil

also chip buckets for scrap metal
are placed throughout the shop &
machining operation of off road
machine.

Oil Dry is stored in drum
1000 hrs. Cutting oil is used
to lubricate the cutting of gears,
& then flows into a trough &
is collected in a holding tank,
Filtered and then recycled. Metal
chips are then put in chip
collection area.

1005 Chip Buckets for dry operations
PIC 2 Southwest Exposure
of Dry chip Storage Area 40cy

KFW

1013 01/4 rags are exchanged by
new ones with Industrial waste
uniform

1016 Heating tanks (2) for
#6 fuel oil are used,
partially aboveground & below ground

1018 Into boiler room
Boiler treatment chemicals (NaOH
solution).

Power house consists of steam generators,
AC/DC area & generators. NO
wastes observed in this area

1024 W/1000 thru Maintenance Shop.
NO swms or AC's identified
Heat treat oil & rust prev. washer
on NW end of Maintenance Shop
to Motor by Amber/Ervinger
to Motor Oil Refinery in
McCool Illinois

102x

Kew

Maintenance Shop generator machine
coolants and oils used
in rolling & lathe turning

1036 Machine Shop #2 & 3

1037 hrs into heat treat shop.

Heat is used to harden steel

Quench oil flows thru

trencher to central storage

area & is closed loop! 20,000 gal tank

Spent Refractory Brick is sent
to BFI East Troy, WI. Ceramic
lined refractory bricks

1044 hrs back to Maint Shop

total of 90 parts washed
on-site (supplied by m/s solv.)

1046 hrs Paint booth operation.

Paint filter, filter

put in solid waste dumpster & shut

103

10

Kew

to BFI

PIC 3 Paint booth filter
changed on measurement arm
manometer. NE exposure
only potential sumu in shop.
Lapping compound is
a fine abrasive compd is
used to make gears &
polish tooth surfaces

1053 hrs. Visited Paint storage area
NO sumus or AVCs noted

1058 hrs Weld Shop. Raw
steel is cut using arc welder
& is ground down

1100 hrs PIC 4 Scrap metal
from Weld Shop shot 39 reynolds
(Work exposure) KEW

104

and sent back to foundry
1103 hrs. Paint booth area
where filter moved to
collect barrel paint

Shot blast is used to rough
finer parts & grind parts (sand)
1106 hrs Paint storage area on
East side of Weld Shop
is locked. NO sumu

1108 hrs Dust collector from
table blast operation (shot blast)
PIC 5 SE exposure -
table blast dust storage
collection. This
material goes w/ foundry sand
to land fill. Area from table blast area

1112 hrs Shot blast storage in
Weld area

105 x2

KEW

106 IX

PIC 6 of shot blast
storage Area next to
shot blast room. Concrete
floor. No cracks visible.
Air emission control includes
collector for waste dust

117 hrs Into Foundry area by
Door east under Storage of metal forms
- Walk through in Corp under Shop
No Arc's occurring in this
area

118 hrs PIC 7 Picture (North)
of Wastewater treatment Area
all of wet scrubber & laundry under
Sludge from this operation
is mixed with sand & polymer
& other materials so solid by mud

Kew

107 IX

then it is sent to landfill

1124 hrs PIC 8 of
Oxygen system sand from
the existing process that
goes to laundry cleaning area.
Laundry building. Platform
floor. No release controls.
except brick wall on one
side. No drains by
this area but there are
2 manholes by this
area ~~located~~ one
is open to sewer system
that goes to treatment
process

1128 hrs. NO Baby Pate Resins
Raw material is stored
outside temporary

Kew

108 ~~108~~

Stand or gravel area. no
release controls. Storm sewer
down next to this area. A
few drums do not have
bung holes & drums are
rusted

1131 hrs PIC 9 NE exposure.
The mats from Landfill Area
are swept up and put in
small 2 cu containers. No
release controls present. Oh gravel
parking area with drums of
oil

1135 hrs Sodium Silicate sludge
(few materials)

Mixer area is used
& contains sand, sodium silicate

KEW

109 ~~109~~

1 papyrus carbonates. Water
is generated which is
shown in PIC 9. Foundry
and mixture!

1138 hrs Foundry Sand Water
PIC 10 East Exposure
gravelled from gravel coatings.
Sinkers Concrete floor is only
release point. NO cracks
in concrete noted. White stain is
~~is sodium silicate stain~~ new
concrete

1142 hrs Slag Box (3-4 in the
oil to sand area)

PIC 11 NE-E exposure of
Slag in metal box. Concrete
floor. No cracks in concrete

KEW

110R

1143 hrs Foundry sand waste
is stored in separate area in the
foundry

1148 hrs PIC 12 Shakeout
sand storage before it goes to
laundry cleaning area is in
foundry. Cracks in concrete. Concrete
there is only yellowish (

1151 hrs PIC 13 Closeup of
shakeout sand storage area

1201 hrs PIC 14 Easy shot of
foundry area. Note sand on concrete
floor & castings laying all over

1206 hrs Shot blast area on west end
is used to clean & blast metal
parts & castings. A dust is
generated from this area

KEW

111R

1207 PIC 15 of last
from shot blast area on
west end of foundry

1208 hrs Metal shop area ^{Scrap} metal stored

1210 hrs PIC 16 of Scrap metal
Storage Area before it
is put back in melting operation

1213 hrs There is a hole by
charging bucket that may
present an OSHA hazard
Next morning area has

numerous amounts of metal
in the bottom of a 22' pit
created in production is
Ferric Chromium (Fe-Cr)
There are 5 ton & 50 ton
melting furnaces.

1221 hrs Shot blast waste area

KEW

112 x

from the #11 shot blast area.

PIC 17. Cracks in concrete floor. Blast stored in span

top metal bucket, no

after release controls,

123 hrs PIC 18 Dust control

collection area for shot (hopper).

Next area (#11) & cleanup

Vacuum for this area. Cracks in

concrete floor. Baghouse collection

areas are on roof. Storm sewer

mainline nearby 7 feet from

Water Sewer.

1224 hrs. Phosphor acid residue were

discontinued about 1980-1981.

Green sand (foundry) was

discontinued in 1986-1987

KFW

113 x

1235 Rawson Avenue Landfill

13th Ave & Rawson

South Milwaukee, WI

WDMP Permit NO. 1882

Falk has been part of Sundstrand

since 1970. End meeting

with Falk representative

1240 hrs Back to Office. End Visit

7-24-92
P. W. Falk
Sundstrand

KFW

(30)

PA/USI:

Falk Corporation

Milwaukee, WI

July 24, 1992

8:15 am Kurt wh. from
Trent Schuler
checked into Falk.

Facility had us sign
safety information.

8:25 Facility reps:
Don Paulus, Env. Eng
Ken Fries, Env
Jack Habiat, Env Eng / Plant Eng

8:30 We ~~seem~~ began meeting in
meeting room above machine shop.

Don Paulus provided (31)

us with a facility layout
map. Space information.

Discussed various EPA ID
numbers for Area Fault facilities.

Facility provided materials
& flow diagram

Facility processes:

I-p-t of charged steel
from recycled scrap
from machine shop
scrap yards.

All into MEST SHOP
see map

r

(32) Incoming raw materials:

Crane

Ferric Manganese

Manganese

Nickel

* Furnace is electric Arc.

5 ton 7' dia

50 ton 10' dia

Heat Treating

Through Hardening

Carbonizing

water quenched

oil quenched

Boiler is fired by natural gas

Laboratories are physical (33)
testing labs.

Two PCB Transformer

will go out of service
within 2 years.

* Enamel Painting

Water Treatment From wet scrubbers

Sand Washing - separate fines
to reuse sand.

- silica Sand.

Sodium Silicate Binder.

reacted w/ propylene
carbonate hardener.

(34) Parts washers w/ mineral
spirits throughout
machine shop.

Weld shop 25% TCE
& mineral spirits

Disposal of Foundry sand
spent refractories
Collection Sand

Trans. - Ducted mineral
Transport
Salem, WI
Wet & dry dust
collectors
Slag from Melt
& Weld Shop

Oils Lubricants grease
Quench
Coolants - compressed oils.
Cutting

Melt in Furnace

Pour

Shake out sand

Riser cuttings

Atc A.Y

Finished Castings

Excess Scrap Goes to
Miller Compressing

Small amount in nonferrous
metals. The scraps from
these are kept separate.

We explained the report
writing process. We explained
some of the provisions
of EPA as far as us
making recommendations. We

(36) cannot make judgments
tell them about AOC or
deficiencies that were.

Milsolv. removes mineral
spirits and recycles.

Safety Kleen removes Paint
Wastes

Milsolv has phase out service
exchange dirty for
clean & recycle dirty.

Safety-Kleen waste on site
~ 3 yrs ago

2 USTs 1987

Diesel
Gasoline

UST were

(37)

Double Walled Tanks
Cathodic Protection
Monitoring Wells.

Piping has secondary walls.
size gas - 1000
Diesel - 8,000

steel.

No monitoring wells other
than those by USTs.

Facility maintains own
storm sewer system. System
pumps over wall. Pumps
are shut off in event
of spill.

②
4:30

Begin Plant Tour.

51 Acres

1300 employees

Empty thing & pickled ⑤
toward Emp. Shop
does not go anywhere
just for collection

SW corner of Property

4:45

Pit 1 SW

Former H2O Storage

Former DSA

Big chrome bucket has water
upstairs

Currently, stored < 90 days

B in curb road

Paints Accumulated in barrels

34 heat sensors to
alarm at gate

~ 10-55-gallon drums / year

Area stores nitrogen material

lapping compound (solid waste)
soldering fluid

Concrete floor

Various virgin products

Expanding joints are
sealed

④

one unknown waste

labeled copper granule

some residential waste accumulates
from employees

Virgin products

Mostly Vircon

Grades of oil

Two Dumpsters east of
DSA. N. dumpster chips
for Miller Comp.

S. dumpster back to Melt shop

Waste O.I. recycled by
Benz O.I.

Volumes of waste O.I. to be
provided.

9:55

left DSA

to Bldg No. 4

(Machining

Lubrication crew collects
waste oil.

10:00

Giant Gear Maching.

Oil drains in completely
enclosed system chips
are filtered out oil is
reused or waste recycled.
Oily chips go to Miller
compressing.

Chips are regularly sent
to melting every 2 weeks
depending on volume

~ 240 cu yd. dumpster

④

(92)

10:07 P. at No. 2 S

Chip accumulation
dust, etc.

left shop No. 4

solid waste:

Compacted by BFI
landfilled.

empty

Catherine Duns located
in abandoned bridge (Lumber Shop)looked in Pattern shop
in

10:18

Boiler Room

(93)

Spill response Wagon

Power House

Heat

AC/DC Gen Generation
for large gens.

A.r compressor

10:22

Old Equipment Room

Above Power House

left Power house
to shop 1.Sew Washing & suit proofing
area.Amber oil / Envelope takes
to motor oil refinery in
McCook, IL.

(22)

Only generates wastes
when tanks are cleaned

Waste oil 55-gallon
drums are treated in
plant. Collect Waste Oil
for use for DSA

10:35

Popped up heat Exch.
Trunking in floor
draw Quench oil to
storage

All Quench oil is stored
20,000 gallon upright
steel tank.

(23)

Fac. bldg uses ceramic
refractory Bricks

Mil/soke has ~ 90 units
of mineral spirits.

Paint Area

Enamel

Filters are removed
when ammeter reaches
differential pressure

Paint Storage

Fire proof

Explosion Proof.

Sprinklers.

⑥

10:55 Entered Weld Shop

NE. corner

Part of NE scrap accumulation
of waste steel.This waste is taken
to Melt shop

11:00

Another Paving area
Center of weld shopDust Skuge Room
Explosion Release Dust

11:05

Dust Collector

Dust is mixed w/
Kendry sand & sent to
landfillthat Blast knocks scale
off of parts.

11:17

Exit Weld shop.

④

Through machine capital's
shop.

WWTP.

Incoming line is from
balcony sand laundry
water from dust collector system's

Discharge to No. 5.

Sludge is pumped out
mixed with sand
to landfill.Polymer is added to solidify
material.

④

11:20

Sweepings Picture taken

Pict No. 6 W.

Blow down from cart's
process.

Also we saw area where
excess sand accumulates
more incidental accumulation
sand spread in roads
along asphalt.

DSA W. Raw material Paste

Not really DSA. Some
waste is not here because
sand is in short down
& undergoes cleaning.

Sweepings Buckets ④

are outside near
WWT. 4x4 buckets

Pict. No. 7

N. Sweepings accumulates
buckets.

11:30

Into Foundry Building

At the end of the day
machines are freed of
raw materials,

Sand is mixed with propylene
carbonate waste is gaskets
substant r.d.

Every day this is calibrated

50

11:37

Pit 8. Foundry sand

accumulation -

Intake area

floos of this area 3

Slag Box

3 or 4 around.

Some have impure metal

Pit 9 NE

Slag Box

11:45

We saw pit area where

large cracks are visible

Shake out sand.

Pit 12 Shake out sand

SE

Pit 13 looking down E

note. Shake out Sand Box

Pit 14 east

51

Overview shot of
Foundry.

Waste From Shot Blast
of E. Foundry is
huddled in skip Baskets

12:05 Pit 15 shot Blast
waste

12:06

Left Foundry to
Melt Shop.

12:07 Pit 16 East

looking into Melt Shop
Storage Bin

can \$50 for

12:10

looked at Furnaces
operation

② left melt stop
to set shot blast

Polyphenol resins operations ②
discontinued in ~80 or 81

12:20. Plot No. 17
No. 11 shot Plot.
Shot Blast Works
Bucket
North.

Green Sand operations discont'd
in ~86 or 87.

Ransom fee \$13th is
land fill
Permitted by WDNR 1882

Plot 18 SW

same are
Picture of shot
blast Bay house's hoppers.
these are taken to
WWTP to mix w sludge.

Falk was purchased in 1970s
wholly owned subsidiary
of Sunstrand.
We conducted a ^{brief} exit
meeting. We received around
facility maps - left.

12:42
